CHITALDRUG DIVISION.

Notice dated the 7th October 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 11th November 1929, for constructing Middle School at Hiriyur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Currency Notes, as earnest money, and be superscribed "Tender for constructing Middle School at Hiriyur, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the list of quantities for constructing Middle School at Hiriyur.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C.yd.	50
2	Burnt stone in clay	C.ft.	2,119
3	Burnt brick in clay	,,	2,593
4	Burnt brick in chunnam arch work	,,	90
5	Burnt brick in chunnam	,,	528
6	Burnt stone slabs 6″ thick dressed	S.ft.	305
7	Teakwood doors pannelled 1¼″ shutters, frame iron clamps and glazed ventilators at top including fittings.	,,	168
8	Teakwood windows pannelled shutters frame ¾″ iron bars, etc., complete.	,,	119
9	Teakwood glazed ventilators over windows	,,	36
10	Teakwood work wrought and put up with wood oiling ...	C.ft.	153·71
11	Roofing with First Class Mangalore tiles on teak reepers, nails, etc., complete.	Sqr.	28·15
12	Ridge tiles set in mortar and cement pointed	R.ft.	134
13	Vallys with teakwood planks, zinc sheets, chunnam and cement gutters, complete.	,,	51
14	Rough plastering one coat ½″ thick well rubbed with trowl, few sand screenings and pebles thrown on the surface to get the effect of rough cast work.	Sqr.	64·74
15	White washing two coats	,,	64 74
16	Chocolate painting three coats	,,	5·90
17	Tarring to wood work	Lump	sum
18	Flooring with Mangalore tiles on 3″ concrete and cement pointing, complete.	Sqr.	13·13
19	Flooring with Cuddapah 1½″ thick slabs on 3″ concrete bed and pointed with cement.	,,	2·82
20	Junglewood eave board with painting plain	R.ft.	2·82
21	Cement pointing to basement	Sqr.	3·26
22	Ornamental work round windows	Lump	sum
23	Chunnam borders	Lump	sum
24	Clearing ground and unforeseen works	Lump	sum
25	Inscription stone	Lump	sum
26	Teakwood finials	Each	3
27	Cutting U shape in stone pillars	Each	10
28	Perforated brick work	Lump	sum